

Bid Clarification Request

(In accordance with ITB 7.1)

Reference Number:
RZ042100-PGG-COM-0015

Dominica Geothermal Risk Mitigation Project Contract

Subject: Bid Clarification 0015 – Scope clarification

Bid Document Clause: Part 2

Detailed description of request

In part 2 page 752/1756 it is stated

“The sites (WW sites) will each require remedial works to bring them up to standard and into their original condition. The scope of work will be determined by the DGDC, with the initial indication being as follows:

- o Site WW-P1: Site improvement, slope stabilisation, drainage works, fencing, security lighting;*
- o Site WW-01: Site fencing, slope stabilisation, drain pond; and*
- o Site WW-R1: Site fencing, security lighting, disposal of material/ general cleanup.”*

Please confirm if this work is to be included in the proposal, given that nowadays there is no specification about the work to be undertaken but a general scope.

Enclosures: None

Response:

The text quoted above from Page 752/1756 is extracted from the Environmental Social Impact Assessment (ESIA). The ESIA document is only included to give the Contractor context to the ESMP requirements which are included in Part 2, Section VII, sub-section 2 “Specification” that details the required scope and specification thereof.

Specific responsibilities for the Contractor resulting from the ESMP have been included in the Specification, Section 1.8.

Clarification on the scope of the perimeter fencing presented in Part 2, Section VII, sub-section 8.1.6 is as follows:

The Contractor shall provide and install a new heavy duty, hot dipped galvanised, 2.4 m high, chain link fence around the following Site areas:

- 1) The main Power Plant and Production Well P1 area defined by the coordinates provided in the Part 2 – Employer’s Requirements, Section VII, subsection 3 “Interface Schedule”, Appendix B “Site Boundary”, Site ID Points PP-01 through PP-38 inclusive. These ID points are also identified on the drawing RZ042100-GN-DRG-0002 provided in Part 2– Employer’s Requirements, Section VII, subsection 1. “Drawings”.
- 2) The reinjection wellpad WW-01 area defined by the coordinates provided in the Part 2 – Employer’s Requirements, Section VII, subsection 3 “Interface Schedule”, Appendix B “Site Boundary”, Site ID Points PT3-1 through PT3-6 inclusive. These ID points are also identified on the drawing RZ042100-ME-DRG-0100, Sheet 6, provided in Part 2– Employer’s Requirements, Section VII, subsection 1. “Drawings”.
- 3) The reinjection wellpad WW-R01 area defined by the coordinates provided in the Part 2 – Employer’s Requirements, Section VII, subsection 3 “Interface Schedule”, Appendix B “Site Boundary”, Site ID Points PT5-1 through PT5-4 inclusive. These ID points are also identified on the drawing RZ042100-ME-DRG-0100, Sheet 7, provided in Part 2– Employer’s Requirements, Section VII, subsection 1. “Drawings”.
- 4) Fencing is not required on the perimeter of the cross country reinjection pipeline corridors.

Enclosures: None

This clarification does not require an Addendum to the Bid Document.

Please acknowledge receipt of this clarification by completing the below information and returning to the sender:

Bidder Company Name _____

Bidder Contact Name _____

Date Received _____